

ADDENDUM

Police Sub-Station and Community Center
13700 Cantrell Road,
Little Rock, AR 72212

Is there asset of drawings available you can email to me and others to be able to better compute the tear out volume? The plans in the report are not readable and I cannot see to print them as they are in the current form. **Not sure what he is reading. You might have to send him another drawing. Ours just show the sample locations, not sure it is pertinent to submitting a bid.**

The documents for the project make to statement concerning project clearance after remediation but does not list a specific methodology and criteria for clearance? **No specified methodology; however it will be by Air-O-Cell, contact samples and visual inspection if the post remediation inspection/sampling is conducted by EMTEC.**

The documents list Kilz as a sealant after remediation, are other products to be allowed? **Yes.**

The scope states "Remove and dispose of the bottom four feet of all interior sheetrock walls." Are we to do the exterior perimeter walls as well? **Yes**

Per the scope, "Performing post remediation inspection and possible re-sampling>" Who will be covering the cost of this re-sampling? Should it be included in our price? **It should be included in your bid price. No requirement in regards to whom performs the post remediation sampling and inspection. If EMTEC perform these services: Cost is \$750.00 per post remediation sampling/inspection.**

Per scope, "Once clearance inspection has passed, perform "put- back." What is the definition/scope of this "put-back?" **That would have to be designed and dictated by the City of Little Rock or the Caradine Companies. Per Caradine Companies/General contractor will re-install dry-wall per construction documents.**

Due to the porosity of the exposed insulation, does the environmental testing company feel that this should be removed in order to obtain a clean air sample? **Remove insulation.**