



Heiple Wiedower
Architects Planners

Addenda No. 2

Reticulated Python Exhibit

Little Rock Zoo

LR Bid # 15-126

April 8, 2015

- Item 1.** See attached sign-in sheet for April 1, 2015 mandatory pre-bid Conference. The Contractors signing in on this sheet are eligible to bid on The Reticulated Python exhibit expansion.
- Item 2.** Refer Specifications Section 00300, Bid Form and Agreement paragraph 3.1 Change the number of days allowable to complete this project from 30 to 35, to include the submittal process time.
- Item 3.** Refer drawing A1.1, the location where the new slab wraps over the existing slab to insure connection between slabs, new slab should lap over existing and provide adequate thickness to minimize cracking.
- Item 4** Refer to drawing A1.2, there should be shown 8" of compacted drainage fill under the new concrete slab.
- Item 5** Refer to drawing A1.2, the material required as coating on the exterior side of the cmu is to be Thorocoat and the clear sealer on the interior of the cmu is to be Thoroseal.
- Item 6** Refer to drawing A1.2, the framing of the existing roof bears on the beams between the round columns and not the building itself. The roof addition will be supported by the new cmu calls and the details of the transitional support between the new roof and the old will be determined in the field.
- Item 7** Refer to drawing A1.2, the new asphalt shingles on plywood decking shown only on the new gable roof addition should be changed to include new asphalt shingles and plywood decking replacing the strip of north facing shakes between the valley formed by new roof and the ridges between the north facing roof and the east & wet sides of the roof. The new decking should be placed over the existing lath and the new shingles are to be extended under the existing ridge shakes to create a weather tight installation.
- Item 8** Refer to drawing A1.1, the access panel noted to be installed on the east side of the exhibit is to be 12" x 12' in size.

- Item 9** Refer to drawing A1.2, the new cmu walls will have vertical reinforcing that will be #4 bars @ 32" O.C.
- Item 10** Refer to drawing A1.2, the plywood noted on the exhibit ceiling is to be interior, paint grade, 3/8" plywood.
- Item 11** Refer to attached City of Little Rock Zoo Contractor Pre-Qualification Questionnaire. If bidders have not already completed and filed this form with the Zoo, it is a requirement that this completed questionnaire be included in the bid documents submitted to the City for this project on bid date.